

SAM750  
LED EXT

# SAM750 LED EXTENSION PRODUCTION REQUIREMENTS

INNOVATIVE MOBILE STAGING



# PRODUCTION REQUIREMENTS

SAM750  
LED EXT

## EQUIPMENT REQUIREMENTS

**5000 LB FORKLIFT or 8000 LB Telehandler**, depending on the selected options. Proper equipment will be specified on supplied Technical Rider

Quantity: 1  
Required Duration: Entire time<sup>1</sup>  
*Forklift example: Caterpillar P5000<sup>2</sup>*  
*Telehandler example: Skytrak 8042*

## 80' MANLIFT

Quantity: 1  
Required Duration: Entire time<sup>1</sup>  
*Example: Genie S-80<sup>2</sup>*

## REQUIRED MAN POWER

### STAGEHANDS

Quantity: 4  
Required Duration: All Load IN and Load OUT days. *Times will be determined and specified on supplied Technical Rider*

### FORKLIFT OPERATORS

Quantity: 1  
Required Duration: All Load IN and Load OUT days. *Times will be determined and specified on supplied Technical Rider*

### RIGGERS

Quantity: 2 x upriggers  
Required Duration: All Load IN and Load OUT days. *Times will be determined and specified on supplied Technical Rider*

## BALLAST REQUIREMENTS

Additional ballast requirements may be necessary upon a rigging plan review.

Quantity: Total ballast amount is 36000 lb. Each ballast block must not exceed a maximum weight of 5000 lb.  
The total amount of ballast must be stackable within a 8'x8' area.  
Required Duration: Entire time<sup>1</sup>

## LODGING & PARKING REQUIREMENTS

### HOTELS

Quantity: 2  
Required Duration: Times to be determined and discussed with Logistics agent

### ON SITE PARKING FOR CREW VEHICLE

Quantity: 1  
Required Duration: Entire time<sup>1</sup>

## ENGINEERING

Client is required to provide a setup and securement procedure for the specific LED product used. This procedure must meet the requirements of the Stageline HWP (high wind procedure) and be approved by a professional engineer.

## GROUND PROTECTION

If the stage is installed on a soft or non-drivable surface, production is responsible for installing proper load bearing ground protection. An accessible, unobstructed and drivable path of 12' x 70' is required for parking the trailer and installation of ballast blocks with the forklift (or telehandler).

<sup>1</sup> Entire time implies from the Setup of structure day 1 through to and including Tear down of structure day 1, as indicated on the supplied Technical Rider.

<sup>2</sup> These are examples of specific makes/brands, the exact product is not mandatory, a similar product will suffice.

827 L'Ange-Gardien Blvd., L'Assomption

Quebec, Canada J5W 1T3

**1 450.589.1063 / North America 1 800.267.8243**

**[stageline.com](http://stageline.com)**

**INNOVATIVE MOBILE STAGING**

